Project Fact Sheet

CENTRAL AVE

Reconstruction Project

Purpose of Project

A major project will begin soon to rebuild one of the primary corridors through the Miamisburg community. Central Avenue from First Street to Twelfth Street will be reconstructed as part of a City roadway grant project.

Reconstruction of this major gateway will replace broken and deteriorated sidewalk, curb and gutter. Storm sewer improvements, utility relocations and installation of new waterline will also be completed. Sub-standard roadway lane widths will be corrected.

Project Description

The roadway will be widened two to three feet and reconstructed from Twelfth Street to the RR tracks, including the installation of new sidewalk curb and gutter, storm sewer, waterline and decorative street lighting.

From the RR tracks to First Street, sidewalk, curb and gutter will be replaced and lawn strips added in the public right-of-way.

New Central Avenue will remain a three-lane configuration with improved tie-ins at each of the existing side streets. The existing traffic signals at Fifth, Sixth and Ninth Streets will be reconstructed, and new asphalt resurfacing will be included.

Additional Elements

Over 20 trees within the public right-of-way (including those in the tree lawn space between the sidewalk and curb) will be removed in order to effectively complete the project. New street trees will be planted as part of the project.

A new City watermain will be installed within the roadway between the RR tracks and Eleventh Street. Existing customers along the corridor will be reconnected to the new main. Vectren will be installing a new gas main on the south side of the roadway and reconnecting individual gas services.

Maintaining Traffic

Eastbound SR725 traffic will be maintained during the project. Westbound SR 725 traffic will be rerouted with a signed detour (See attached). The side streets along Central Ave. will typically remain open with temporary closures during tie-in work.

Cost/Schedule

The project will be bid in April with construction scheduled to begin in May. The project is funded with a $1.4 M Ohio Public Works Commission grant, along with ODOT resurfacing and local City matching funds.

Questions?

City Engineering

engineer@cityofmiamisburg.org

937-847-6531

CITY OF MIAMISBURG
OHIO'S STAR CITY